

## Batiquitos (B3) Force Main Discharge Section Replacement Project Bid Schedule

<b>Bid Project</b>	<b>15 APR 19</b>
<b>Project Walk-Thru</b>	<b>24 APR 19</b>
<b>Questions Due</b>	<b>01 MAY 19</b>
<b>Addendum (If Necessary)</b>	<b>07 MAY 19</b>
<b>Bid Opening (2:00 pm)</b>	<b>14 MAY 19</b>
<b>IEC Recommendation Ltr</b>	<b>24 MAY 19</b>
<b>Engineering Committee</b>	<b>05 JUN 19</b>
<b>Board Approval</b>	<b>12 JUN 19</b>

### Project Information:

**Engineer's Estimate: \$485,000**

Description: Install approximately 720 linear feet of 24-inch polyvinyl chloride (PVC) sewer force main and rehabilitation of three manholes at the discharge end of the project. Project includes all saw cutting, dewatering, potholing of existing utilities, Water Pollution Control Drawings creation and implementation, abandonment and/or removal of exist 24-inch main, removal and replacement of roadway surfaces, including sawcutting and removal of concrete roadway surfaces up to two feet thick, trenching, shoring, dewatering, pipe, bedding, compaction, backfill, off-site disposal of all construction waste pursuant to applicable law, performing all connections between new pipelines and the existing system; completing all trench resurfacing and site restoration; removing the existing sewer facilities as shown on the plans; installing corrosion protection; obtaining all required permits; and completing all traffic control and to restore disturbed areas and surface improvements back to original conditions.

<b>New 24" PVC Pipe</b>	<b>720 ft</b>
<b>Cured-In-Place Manhole Liner (CIPML)</b>	<b>3 manholes</b>

**Bid Packets available** from Mesa Reprographics, 5560 Ruffin Road, San Diego, California 92123, (858) 541-1500 or on line at <http://www.mesareprographics.com/clients/lwwd7/>